



CONFIGURATION: THE INSTALL HANDOFF

PREPPING FOR THE ELECTRICIAN:

Now for the easy part. You have designed, ordered and received your Lutron products. Using the site survey guide from step 2, group the devices by location, following the gang order from left to right. Band the groups together and place them in front of the actual locations in the home as you walk through with the electrician. After the installation is complete, you can install the repeater(s), plug in the modules and Pico tabletops, and begin configuration. For those dealers that must know everything, we have included a link at the end of the document to a wiring tool provided by Lutron.

1. Referencing the Site Survey Guide, prep the products for delivery. Group the switches, dimmers, and in-wall PICOs by location. Best practice is to band them in order from left to right as you want them installed in the wall box.



2. Schedule a meeting with a certified electrician to deliver the product to him and walk through the home.
3. Walk through the site with the electrician, and place the equipment bundles in their correct locations. This gives the electrician the opportunity to ask you questions. (You will install the table top controls, plug-in dimmers and switches, and the repeater(s) later, when you are ready to start configuration.)





4. Instructions are included in all boxes, so a certified electrician should be able to complete the job. They may have questions if you planned for PICO Controls in wall locations.





Lutron recommends that all installations be performed by certified electricians. However, if you are curious how it is done, [here is a link to directions on how to install a dimmer.](#)